

CLASSIFICATION

CENTRAL INTELLIGENCE AGENCY

REPORT

INFORMATION REPORT

CD NO.

25X1

COUNTRY East Germany

DATE DISTR. 18 November 1955

SUBJECT VEB Transformatoren- und Röntgenwerk
Dresden (Tuft) Production and Personnel

NO. OF PAGES 4

PLACE
ACQUIREDNO. OF ENCLS.
(LISTED BELOW)

25X1

DATE OF
INFO.SUPPLEMENT TO
REPORT NO.

THIS IS UNEVALUATED INFORMATION

25X1

1. In March 1955, [redacted] at the [redacted] and Roentgen [redacted] for a [redacted] with double-concentric winding. The development of a transformer for 3,000 kVA and 6 kV/1 MV has been completed. The transformer fitted with a double-concentric winding was to be much lighter than the older one and was to have a 30 to 35 percent higher efficiency. Measurements made on the new transformer showed favorable results. Before the transformer was built, a so-called "phantom", that is, a model of the transformer at reduced dimensions, was manufactured. Taking into consideration the smaller dimensions, - usually the phantom was one-twentieth the size of the transformer to be built - the phantom had to yield the same results as the transformer itself. In the case of the transformer under development at the plant, the phantom tested proved less efficient than expected. The reason for this failure was unexplained. The weight of the transformer in standard size make will be 20 tons. On the basis of the previous design, the weight of such a transformer would have been 35 to 40 tons.

25X1

The transformer of cascade stages II and III of the testing installation were not yet completed.¹

2. A betatron designed for a voltage of [redacted] of 1 r/m was also under development. [redacted] successfully completed and the output [redacted] 1955. The betatron [redacted]

[redacted] Dr. Winter, efforts had been made to develop a similar betatron at the [redacted]. In Jena, Professor Dr. Eckart tried [redacted] betatron for 1.2 megavolts with a cold cathode [redacted] basic circuit diagram of the impulse [redacted] development was unsuccessful because [redacted] cathode. Professor Eckart is said [redacted] 30 megavolt betatron based on a principle applied by the Swiss firm of Brown [redacted] Dr. Winter was charged with developing [redacted] this betatron. The designs for this [redacted] at the [redacted]

25X1

CLASSIFICATION

STATE	NAVY	ARMY	DISPATCH
ARMY	NAVY	ARMY	DISPATCH

25X1

25X1

- 2 -

obtaining suitable cathodes for t [REDACTED]
by lack of suitable radiation mea [REDACTED]
counters.

3. The following development work was also being conducted at [REDACTED]

25X1

- a. Development of a van de Graaf generator for [REDACTED]
with one accelerating tube. [REDACTED]

25X1

The generator was completed except for the accelerating tube. Work on the generator was suspended in February 1955 because of a shortage of funds. The generator will be furnished to the institute headed by von Ardenne in Dresden.

- b. Development of a set designed to measure high frequencies fitted with 6-spark gaps (6-fach-Funkenstrecken) in hydrogen atmosphere. The set is scheduled to be furnished to a Moscow institute and is said to be a copy of an equipment designed by a Stuttgart physicist. Oscillographs are also said to be part of the equipment. Sparks in the 6-fold spark gap (6-fach Funkenstrecke) in H₂ atmosphere are photographed. It appears that the development work is making slow progress.

- c. Development of radiation measuring sets and Geiger - Mueller counters.

- d. Construction of a [REDACTED] 3 MV and an output [REDACTED] 3,000 KVA testing transformer is scheduled to be completed in 1956. Subsequently, the second and third transformers are to be built. A special group of engineers is charged with this development and the equipment will be delivered to the USSR.

4. No work was being done on the development of standard transformers.

5. The production program [REDACTED] included transformers of various types, direct-voltage and shock potential [REDACTED] oscillations, X-ray sets for medical purposes and other similar equipment.

6. The [REDACTED] Dresden had accumulated debts to the amount of 7 million DME, in March. The [REDACTED] had stopped buying transformers because of the poor quality of the transformers delivered. The volume of other exports was very low. The scheduled 1955 output expressed in factory sales prices was as follows:

Transformers priced at about	15 million DME
Converters " " "	6 " 7 " "
Various installation priced at about	6 " to 7 " "
X-ray sets priced at about	12 " "
Other type quantity production priced at about	3 " "

Only in the fields of X-ray sets and quantity production [REDACTED] correspond to the [REDACTED] of the [REDACTED] in hand [REDACTED]

7. There was a shortage of [REDACTED] at the plant. This situation [REDACTED] the poor [REDACTED] of the transformers manufactured at the [REDACTED]

[REDACTED] Institute for Ultramicroscopy and Physics of Charge Carriers (Versuchsinstitut fuer Uebermikroskopie und Physik der Ladungstraeger).

Comment. For 1955 production plan of TdR, See Annex 2.

25X1

25X1

25X1

Annex 1

25X1

Plant manager: [REDACTED]

Technical adviser to the transformer department: [REDACTED]

Chief designer of the X-ray equipment department: [REDACTED]

Chief designer of the transformer department: [REDACTED]

[REDACTED] Winter, who was assisted by Brey [REDACTED]

Technical director: v. Se [REDACTED]

Production chief: Herfort, "main dispatcher"/ production trouble shooter

Main technologist: [REDACTED]

Sales department: [REDACTED]

Chief of the X-ray [REDACTED]

In charge of the quantity production: [REDACTED] and Bahrman

Chief of the transformer department: Graichen; chief designer of this department was Lange

Chief of the converter department (Wandler Werk): [REDACTED]

Chief of the installations department (Anlagenwerk): [REDACTED]

In charge of the delivery plant: Herfort.

Laboratories used for development work were headed by Dr. Gasbler, Schubert and Dummer. Brey worked as a designer in this development department and Hudelist was technical chief.

25X1

-4-

Annex 2

25X1

25X1

1. Transformers designed for outputs ranging from 100 VA to 100 MVA in about 5,000 different units. The transformers manufactured are not standardized. No rectifying transformers are being built. The different groups of transformers under production have the following reference number:

- 11: transformers for transformer plants and for the electric power supply;
- 12: mobile transformers mounted on railroad cars;
- 13: furnace transformers for smelting furnaces;
- 14: testing transformers designed for voltages of up to 1 MV and output of up to 3,000 KVA;
- 15: converters of all types.

2. Installations.

The following reference numbers were in use:

- 21: direct voltage installations of up to 3 MV with Greinach (sic) type switching arrangement and not fitted with accelerating tubes. These installations were required for [redacted] of installations and the acceleration of protons and [redacted]
- 22: Shock potential installations up to 4 MV or 100 KW/s or 100 K. The installations were required for the testing of shock voltage occurring in transformers and high tension installations. The newest installation developed was up to international standards.

3. X-ray sets:

The following reference numbers were in use:

- 31: sets used for diagnostic purposes, fitted with up to 6 tubes.
- 32: therapeutic sets.
- 33: VHF radio therapeutic sets.
- 34: electric equipment required for surgical purposes.

4. Quantity production.

The following reference numbers were in use:

- 41: [redacted]
- 42: [redacted] production 40,000 units. [redacted] delivered, however, [redacted] 10,000 - [redacted] produced.
- 43: Infra-red sets for medical purposes, scheduled 1955-production 10,000 units.

25X1

25X1

INFORMATION REPORT

CD NO.

25X1

COUNTRY East Germany

SUBJECT VEB Transformatoren- und Roentgenwerk
Dresden (TuR) Production and Personnel

DATE DISTR. 18 November 1955

NO. OF PAGES 4

PLACE
ACQUIREDNO. OF ENCLS.
(LISTED BELOW)DATE OF
INFO.SUPPLEMENT TO
REPORT NO.

25X1

THIS DOCUMENT CONTAINS INFORMATION CONCERNING THE COMMON DEFENSE
OF THE UNITED STATES, WHICH IS SUBJECT OF TITLE 18, SECTIONS 793
AND 794, OF THE U. S. CODE, AS AMENDED. ITS TRANSMISSION OR REVEL-
ATION OF ITS CONTENTS TO AN UNAUTHORIZED PERSON IS PROHIBITED BY LAW. THE REPRODUCTION OF THIS FORM IS PROHIBITED.

THIS IS UNEVALUATED INFORMATION

25X1

1. In March 1955, development work was under way at the Transformatoren- und Roentgenwerk Dresden (TuR-formerly TRARO) on a test transformer for a three-MV installation designed for cascade connection and provided with double-concentric winding in symmetric arrangement. The development of a transformer for 3,000 kVA and 6 kV/1 MV has been completed. The transformer fitted with a double-concentric winding was to be much lighter than the older one and was to have a 30 to 35 percent higher efficiency. Measurements made on the new transformer showed favorable results. Before the transformer was built, a so-called "phantom", that is, a model of the transformer at reduced dimensions was manufactured. Taking into consideration the smaller dimensions - usually the phantom was one-twentieth the size of the transformer to be built - the phantom had to yield the same results as the transformer itself. In the case of the transformer under development at the plant, the phantom tested proved less efficient than expected. The reason for this failure was unexplained. The weight of the transformer in standard size make will be 20 tons. On the basis of the previous design, the weight of such a transformer would have been 35 to 40 tons.
- The transformer of cascade stages II and III of the testing installation were not yet completed.

2. A betatron designed for a voltage of 10 megavolts and a radiation intensity of 1 r/m was also under development at the plant. The development work was successfully completed and the output demanded was reached during tests made in March 1955. The betatron was tested for 15 hours without a stop.

According to Dr. Winter, efforts had been made to develop a similar betatron at the Physics Institute at Jena University. In Jena, Professor Dr. Eckart tried for three years to develop a betatron for 1.2 megavolts with a cold cathode. The betatron utilized the basic circuit diagram of the impulse betatron designed by Philips. The development was unsuccessful because of difficulties experienced with the cathode. Professor Eckart is said to be going to develop a 30 megavolt betatron based on a principle applied by the Swiss firm of Brown Boveri & Cie.

Dr. Winter was charged with developing the six-leg core (6-Schenkel-Kern) for this betatron. The designs for this betatron had been completed at the TuR in Dresden. Dr. Winter continuously complained about the unreasonableness of the demands made by Professor Eckart. Eckart was greatly interested in

25X1

SECRET

CLASSIFICATION

STATE	<input checked="" type="checkbox"/> NAVY	<input checked="" type="checkbox"/> NSRB	<input checked="" type="checkbox"/> DISTRIBUTION						
ARMY	<input checked="" type="checkbox"/> AIR	<input checked="" type="checkbox"/> FBI	<input checked="" type="checkbox"/> AEC	<input checked="" type="checkbox"/> X					

25X1

25X1

- 2 -

obtaining suitable cathodes for the TuR. Development work was hampered by lack of suitable radiation measuring devices, dosimeters and tube counters.

3. The following development work was also being conducted at TuR:

- a. Development of a van de Graaf generator for 2 megavolts, fitted with one accelerating tube.

The generator was completed except for the accelerating tube. Work on the generator was suspended in February 1955 because of a shortage of funds. The generator will be furnished to the institute headed by von Ardenne in Dresden.²

25X1

- b. Development of a set designed to measure high frequencies fitted with 6-spark gaps (6-fach Funkenstrecken) in hydrogen atmosphere. The set is scheduled to be furnished to a Moscow institute and is said to be a copy of an equipment designed by a Stuttgart physicist. Oscillographs are also said to be part of the equipment. Sparks in the 6-fold spark gap (6-fach Funkenstrecke) in H₂ atmosphere are photographed. It appears that the development work is making slow progress.

- c. Development of radiation measuring sets and Geiger - Mueller counters.

- d. Construction of e A.G. (sic) testing transformers designed for a voltage of 3 MV and an output of 3,000, 5,000 and 10,000 KVA respectively. The 3,000 KVA testing transformer is scheduled to be completed in 1956. Subsequently, the second and third transformers are to be built. A special group of engineers is charged with this development and the equipment will be delivered to the USSR.

4. No work was being done on the development of standard transformers.

5. The production program of TuR included transformers of various types, direct-voltage and shock potential installations, X-ray sets for medical purposes and other similar equipment.³

6. The TuR at Dresden had accumulated debts to the amount of 7 million DME, in March. The USSR had stopped buying transformers because of the poor quality of the transformers delivered. The volume of other exports was very low. The scheduled 1955 output expressed in factory sales prices was as follows:

Transformers priced at about	million	15 million DME
Converters " " "	6 to 7	" "
Various installation priced at about	6 " to 7	" "
X-ray sets priced at about	12	" "
Other type quantity production priced at about	3	" "

Only in the fields of X-ray sets and quantity production did the orders on hand correspond to the production capacity of the plant. Otherwise, orders on hand did not warrant full employment.

7. There was a shortage of skilled workers at the plant. This situation mainly explained the poor quality of the transformers manufactured at the plant.

1. Comment. For organizational set-up of TuR, see Annex 1.

25X1

2. Comment. The institute in Dresden headed by von Ardenne is the Research Institute for Ultramicroscopy and Physics of Charge Carriers (Forschungsinstitut fuer Uebermikroskopie und Physik der Ladungstraeger).

3. Comment. For 1955 production plan of TuR, See Annex 2.

25X1

S-E-C-R-E-T

25X1

SECRET

25X1

-3-

Annex 1

Organizational Set-up and Personnel of VEB Transformatoren- u. Roentgenwerk Dresden.

Plant manager: Hermann Farnula

Technical adviser to the transformer department: Wuefling
 Chief designer of the X-ray equipment department: Horst Beper
 Chief designer of the transformer department: Bahrmann
 Chief of the development department: Dr. Winter, who was assisted by Brey
 Business manager: Guenther Zimmermann.
 In charge of labor affairs: Alfred Kessner
 Technical director: v. Schiessl
 Production chief: Herfort, "main dispatcher"/ production trouble shooter
 Main technologist: (unknown)
 Sales department: Victor Dunkel, who was assisted by Kohl and Beger
 Chief of the X-ray department: Willy Protz
 In charge of the quantity production: Hudelist and Bahrmann
 Chief of the transformer department: Graichen; chief designer of this department was Lange
 Chief of the converter department (Wandler Werk): Neubert
 Chief of the installations department (Anlagenwerk): Kurt Zirkel
 In charge of the delivery plant: Herfort.

Laboratories used for development work were headed by Dr. Gaebler, Schubert and Dummer. Brey worked as a designer in this development department and Hudelist was technical chief.

SECRET

25X1

SECRET

25X1

Annex 2

25X1

Production Program of the VEB Transformatoren- u. Roentgenwerk Dresden as of March 1955.

1. Transformers designed for outputs ranging from 100 VA to 100 MVA in about 5,000 different units. The transformers manufactured are not standardized. No rectifying transformers are being built. The different groups of transformers under production have the following reference number:

- 11: transformers for transformer plants and for the electric power supply;
- 12: mobile transformers mounted on railroad cars;
- 13: furnace transformers for smelting furnaces;
- 14: testing transformers designed for voltages of up to 1 MV and output of up to 3,000 KVA;
- 15: converters of all types.

2. Installations.

The following reference numbers were in use:

- 21: direct voltage installations of up to 3 MV with Greinach (sic) type switching arrangement and not fitted with accelerating tubes. These installations were required for the testing of installations and the acceleration of protons and deuterons
- 22: Shock potential installations up to 4 MV and 100 MKW/s or 100 KW/ms. The installations were required for the testing of shock voltage occurring in transformers and high tension installations. The newest installation developed was up to international standards.

3. X-ray sets:

The following reference numbers were in use:

- 31: sets used for diagnostic purposes, fitted with up to 6 tubes.
- 32: therapeutic sets.
- 33: VHF radio therapeutic sets.
- 34: electric equipment required for surgical purposes.

4. Quantity production.

The following reference numbers were in use:

- 41: washing machines, [redacted] scheduled 1955 production, 40,000 units;
- 42: steel cases (Stahlbaukasten) scheduled 1955 production 40,000 units. It was believed, however, that only 10,000 - 15,000 units would be produced.
- 43: Infra-red sets for medical purposes, scheduled 1955 production 10,000 units.

25X1

SECRET

25X1